



SHED CENTER

*Office (406) 727-2425 *Email sales@montanashedcenter.com *Fax (888) 727-5621 *www.montanashedcenter.com

"STORAGE YOUR WAY"

Portable Log Cabins all of MT area Retail Pricelist.

To close in, insulate, seal the standard 6' porch area or add front loft, add \$20 sq.ft. of additional insulated area.

Shipping to ID, KAL, LB, EK display areas will incur additional shipping cost to the standard price.

All Portable Log Cabins must be built in our Montana Factory and shipped into ID.

12' wide add \$800, 14' wide add \$1100, 16' wide add \$1800.

Sizes	Dearborn	Cascade	Glacier
12x22	\$15,019	\$29,694	\$38,010
12x24	\$16,129	\$30,909	\$39,331
12x26	\$17,249	\$32,135	\$40,663
12x28	\$18,359	\$33,350	\$41,984
12x30	\$19,859	\$34,956	\$43,695
12x32	\$20,979	\$36,182	\$45,026
14x22	\$17,029	\$31,897	\$40,727
14x24	\$18,539	\$33,530	\$42,484
14x26	\$20,039	\$35,154	\$44,230
14x28	\$21,539	\$36,777	\$45,977
14x30	\$23,039	\$38,400	\$47,723
14x32	\$24,549	\$40,033	\$49,479
14x34	\$26,049	\$41,656	\$51,226
14x36	\$27,549	\$43,280	\$52,972
14x38	\$29,049	\$44,903	\$54,719
14x40	\$30,559	\$46,536	\$56,475
14x42	\$32,059	\$48,159	\$58,221
14x44	\$33,559	\$49,782	\$59,968
14x46	\$35,059	\$51,406	\$61,714
16x22	\$21,129	\$36,191	\$45,535
16x24	\$22,879	\$38,082	\$47,566
16x26	\$24,699	\$40,042	\$49,668
16x28	\$26,519	\$42,003	\$51,769
16x30	\$28,339	\$43,964	\$53,871
16x32	\$30,169	\$45,935	\$55,983
16x34	\$31,989	\$47,896	\$58,084
16x36	\$33,809	\$49,856	\$60,186
16x38	\$35,629	\$51,817	\$62,287
16x40	\$38,159	\$54,488	\$65,099
16x42	\$39,999	\$56,469	\$67,221
16x44	\$41,849	\$58,460	\$69,352
16x46	\$43,689	\$60,440	\$71,474
16x48	\$46,499	\$63,391	\$74,565
16x50	\$48,379	\$65,412	\$76,727
16x52	\$50,269	\$67,443	\$78,899
16x54	\$52,149	\$69,464	\$81,060



Dearborn Features

- Basic Electrical: 12 connections+panel
- 2x6 T&G Log Siding with stain/sealer
- 2x6 T&G Flooring
- 2x6 T&G ceiling
- 4x6 PT Skids (12'=5 *14' & 16'=7)
- 6' x width of building porch included in listed length w/railing
- Timber frame inside
- All siding and flooring is screwed
- NO interior sealer
- 4 windows 30x40 (with grids)
- R-13 Fiberglass insulation in floor
- R-27 Insulation in walls and ceiling
- 8' deep loft inside x width of building
- Includes 18x20 slider window

Cascade Features add To Dearborn series

- Standard Kitchen (up to 10' of base cabinets only with sink)
- Extra wiring for bath/kitchen
- Standard bath with sink, shower, toilet, water heater RTE 13 plumbing access, fan.
- Sealer on interior floor, walls, and ceiling.

NO GUARANTEES ON DOUG FIR FLOOR

Glacier Features add to Cascade and Dearborn

- Upgraded Kitchen with 10' base and 8' upper cabinets + 36" lower corner cabinet and 24" upper corner cabinet
- Standard bath with sink, shower, toilet, water heater RTE18, vent fan or window
- Washer and Dryer hookups in bathroom, 2x4 bed closet with one door
- Bedroom package includes smoke detector, 2 windows (one egress)
- Loft over front porch 8' deep x width of building
- Baseboard electric heat • Laminat floor (New for 2017)



10' Base Cabinets
Cascade Series Kitchen

Glacier series kitchen



Delivery Requirements for all cabins over 14x34

Site MUST be accessible with a Semi Tractor and Trailer. There must be 110' minimum directly in front of one END of where building is set for truck to pull away from building. If this requirement cannot be met, customer must provide a crane service to set the building. Can be shipped to the entire Northwest USA. Site prep is Homeowner's responsibility. **Compacted Gravel base or Cement slab required.**